

1614 Dresden St.

1. Install new vinyl replacement windows in home. The new windows are to be white double hung vinyl replacements. The new windows are to have screens included. The new window is to be American brand or equal in quality. Include all necessary framing, insulation & sealing to the interior & exterior and aluminum trim work for the new replacement windows. The new aluminum trim work is to be white. The new bathroom window is to have frosted glass. Include all necessary materials to complete the project.

2. Replace the existing front storm door. The new replacement storm door is to be a white Midview storm door with a screen. Allow \$275 for the new door. The existing rear entry door is to have a new Kwikset deadbolt assembly installed and is to be keyed to match the existing door lock. The existing rear entry door and existing storm door is to be adjusted so each door opens and shuts as they should and seal correctly. Include all materials and labor needed to complete.

3. Remove existing gutters and downspouts. Install new white 6-inch seamless gutters on the home completely. Install all new white downspouts complete. Install all new 30' concrete splash blocks at all downspouts to assure water flows away from the foundation around the home. Assure all gutters around the home are free of debris and are flowing correctly. Provide all necessary material to complete this work. Homeowner to install gutter guard after work is completed, if wanted.