
| | REINFORCING STEEL FOR MANHOLES | | | | | | | | | | | | | | | | |
|------|--------------------------------|-----|------------|------|--------|---------------------|-----|------|---------------|---------------------|------------|------|--------|----------------------|-----|------|--|
| | M.H. FOR 27" TO 42" | | | | | M.H. FOR 48" TO 60" | | | | M.H. FOR 66" TO 84" | | | | M.H. FOR 90" TO 108" | | | |
| BARS | LENGTH | N□. | SPA | SIZE | LENGTH | ND. | SPA | SIZE | LENGTH | ND. | SPA | SIZE | LENGTH | ND. | SPA | SIZE | |
| В | 8′-0″ | 10 | 9″ | No.5 | 8'-0" | 12 | 9″ | No.5 | 8'-0" | 16 | 9″ | No.5 | 8'-0" | 19 | 9″ | No.5 | |
| B1 | 6′-9″ | 12 | 9″ | No.5 | 8'-6" | 12 | 9″ | No.5 | 11'-0" | 12 | 9″ | No.5 | 13'-3" | 12 | 9″ | No.5 | |
| Е | 7′-3″ | 3 | 2" | No.5 | 7′-3″ | 3 | 2" | No.5 | 7′-3″ | 3 | 2" | No.5 | 7′-3″ | 3 | 2" | No.5 | |
| Н | 8′-6″ | 22 | 6″ | No.5 | 8′-6″ | 33 | 6″ | No.5 | 8′-6″ | 41 | 6″ | No.5 | 8′-6″ | 58 | 6″ | No.5 | |
| L | 3'-0" | 16 | 12" | No.5 | 3'-0" | 16 | 12" | No.5 | 3'-0" | 16 | 12" | No.5 | 3'-0" | 16 | 12" | No.5 | |
| Т | 1′-3″ | 16 | 6″ | No.5 | 3'-0" | 16 | 6″ | No.5 | 5′-3 ″ | 16 | 6 | No.5 | 7′-6″ | 16 | 6″ | No.5 | |
| V | 5′-0 ″ | 16 | 6″ | No.5 | 6′-9″ | 16 | 6″ | No.5 | 9'-0" | 16 | 6 " | No.5 | 11'-6" | 16 | 6″ | No.5 | |
| V1 | 4′-9″ | 16 | 6 " | No.5 | 6′-6″ | 16 | 6″ | No.5 | 8'-9" | 16 | 6″ | No.5 | 11'-3" | 16 | 6″ | No.5 | |



NOTES:

- 1.) See Plans for casting size and type.
- Manhole steps shall be cast iron or plastic coated steel, weighing not less than ten pounds each.
- 3.) Concrete for poured base, box, and collars shall be 3500 psi concrete. Precast concrete shall conform to ASTM C-478.
- 4.) Where headroom is limited, a precast cover may be substituted for the eccentric cone shown. See Detail B-4 for detail.
- 5.) Base may be precast or poured in place concrete. When precast base is used a 6" base of No. 53 crushed stone will be required and all connecting pipes shall be grouted with a 6" concrete collar.
- 6.) In unpaved areas use a 6" concrete collar to hold grade rings and casting in place.
- 7.) The M.H. shall be backfilled per plans and specifications.
- 8.) The cost of the manhole shall include all of the above items.

DETAIL B-5b

Rectangular Manhole for 27" to 108" Diameter Pipes No Scale (Rev. Date 09/01/04)