



Notes:

- 1.) Expansion joints should be placed a max. of 48" on center, using 1/2" preformed joint filler material, for curbs and sidewalks.
- 2.) Preformed 1/2" joint filler material shall be placed around all manholes, utilities, and between the sidewalk and any fixed structures.
- 3.) Concrete for sidewalk shall be 3500 psi concrete.
- 4.) Elastomeric sealant shall be used on joints containing 1/2" joint filler material.
- 5.) Maximum cross slope on sidewalk shall be 2%.
- 6.) The cost of the sidewalk shall include all of the above items.
- 7.) Where site infeasibility precludes construction to standard sidewalk width, such width may be decreased to a minimum of 3'-0" (e.g. Obstructions such as utilities, trees, etc.).

DETAIL D-4

Miscellaneous Sidewalk and Curb Details
 Scale 1/4"=1' (Rev. Date 4/03/07)